SHIMOGA DIVISION.

Dated 18th July 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th August 1904, for improving Salur anikat and channels in Shikarpur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Salur anikat and channel in Shikarpur Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Western Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Description of work.	*Unit of work.*	*Rate per unit.*
Removing brick, masonry, etc.	L. S.	...
Burnt brick in surki mortar	C. ft.	2,259
Burnt stone slabs, dressed	S. ft.	690
Do undressed	„	435
Burnt brick in ordinary mortar	C. ft.	1,041
Burnt stone slabs, dressed with cement pointing	S. ft.	18
Rough stone work, new	C. yds.	339
Dismantling and re-building old stone work	„	817
Packing with jelly	„	286
Stone jelly concrete	C. ft.	70
Concrete	„	1,719
Plastering in surki mortar	Sqr.	19·40
Do in ordinary mortar	„	5·72
Examining and closing leakages	L. S.	...
Dismantling old stone work	C. yds.	124
Earthwork	„	14,287
Rough stone in surki mortar	C. ft.	4,536
Turfing	Sqr.	1,528·00
Teakwood planks	C. ft.	6
Repairing the gear with iron work, etc.	L. S.	...
Gravelling	C. yds.	42
Clearing jungle and site	L. S.	...
*Constructing sluices	„	...
Repairing road, tunnel and re-constructing, etc.	„	...
Removing pipe sluices and repairing	Each	23
Mangalore pipe 9" diameter	R. ft.	30
*Earthwork	C. yds.	406
Brick in surki mortar	C. ft.	696
Plastering surki mortar	Sqr.	6·50
Rough stone work	C. yds.	45
Turfing	L. S.	...
Stone slabs	S. ft.	28
Concrete in surki mortar	C. ft.	169
Excavating channels, etc.	L. S.	...
Repairing masonry works and clearing site	„	...
Examining and closing leak	„	...

K. KRISHNAIENGAR, *Executive Engineer.*